BRUHAT BENGALURU MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division,

Schedule-B

NAME OF WORK: Improvements to Roads and drains at Surya Enclave roads and other roads in ward No 12, Shettyhalli Sub Division

Sl No	Description of work	Unit	Qty	Sanctioned rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2018-19, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per specifications and as per the direction of Engineer-in charge of the work.	Cum	1281.92	211.79	Rupees Two Hundred Eleven And Paise Seventy Nine Only
2	Plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scafofolding and centeringetc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	153.47	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	16.28	5647.68	Rupees Five Thousand Six Hundred Forty Seven And Paise Sixty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 056

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

4	Providing laying palin / reinforced cement concrete for side Drain using M20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., completet excluding cost of steel ae per MMORTH specification No 1500, 1700, 2200. including cost of materials, labour, HOM etc., complete as per specifications and as per the direction of Engineer-in charge of the work.	Cum	341.80	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical etc., complete as per specifications and as per the direction of Engineer-in charge of the work.	Tonne	19.03	72316.38	Rupees Seventy Two Thousand Three Hundred Sixteen And Paise Thirty Eight Only
6	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	sqm	1082.25	1651.00	Rupees One Thousand Six Hundred Fifty One Only
7	Providing and laying Pre Cast Drain Cover slabs of 250mm thick for drain in cement concrete m 20 using graded ganite jelly 20 mm and down size with steel reinforcement, including form work, lift charges, curing and concrte finished surfaces on both side etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	sqm	73.50	5241.00	Rupees Five Thousand Two Hundred Forty One Only
8	Providing and fixing street Name boards etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Nos	134	5203.00	Rupees Five Thousand Two Hundred Three
9	Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	332.15	727.16	Rupees Seven Hundred Twenty Seven And Paise Sixteen Only
10	Providing Laying, fixing & Installation of Computerized Stickers to the name boards including erasing Old Stickers Cleaning the Name board & applying neatly computerized stickers to the Name board etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Nos	268.00	600.00	Rupees Six Hundred Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 056

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

11	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to<tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and Complete as per specifications. MORTH Specification No.301 etc., complete as per specifications and as per the direction of Engineer-in	Cum	825.00	43.46	Rupees Forty Three And Paise Forty Six Only
12	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel I murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	618.75	344.50	Rupees Three Hundred Forty Four And Paise Fifty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 056

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.